



Addendum #1 – 2016 Winter Sewer Replacement Project

1. There is not a Bid Bond required for the project.
2. The Contractor will only be responsible for replacing the asphalt with cold patch and will not be required to return and perform a HMA patch in the spring.
3. If abandoned the sewer manhole 1028 will be required to be filled with sand and the abandoned sewer line capped.
4. One Proctor will be required to determine compaction requirements and is the responsibility of the Contractor.
5. Sewer replacement will occur in live conditions and Contractor will need to include the cost to accommodate this situation in the 8" Sewer Pipeline Item.
6. Testing by the City will include monitoring of construction and use of the City's sewer camera to inspect completed sewer line prior to acceptance. Due to the nature of a live sewer replacement an air test and lamp test will not be required.
7. Questions regarding the project will need to be received by today Tuesday, November 8th at 4:00pm. The City will send out a second addendum (if required) by 5:00pm on the same day Tuesday, November 8th.

Bid deadline remains the same